Maryland Historical Trust State Historic Sites Inventory Form

Magi No. 0507855804

DOE __yes __no

| 1. Nam | le (indicate p | oreferred name) | | |
|--|---|--|-----------------------------|--|
| | | | | · |
| historic | Robert and Mai | ry Trott House | | |
| and/or common | | | | |
| 2. Loca | ation | | | |
| street & number | 2410 Plum 1 | Point Road (Maryl | and Route 263) | not for publication |
| city, town Pa | rran | X vicinity of | congressional district | |
| state Ma | ryland | count | y Calvert Cou | nty |
| 3. Clas | sification | | | |
| Category district _X_ building(s) structure site object | Ownership public private both Public Acquisition in process being considered not_applicable | Status X occupied unoccupied work in progress Accessible X yes: restricted yes: unrestricted no | entertainment government | museum park X private residence religious scientific transportation other: |
| 4. Own | er of Prope | erty (give names | and mailing address | es of <u>all</u> owners) |
| name M | r. and Mrs. Rol | ert E. Trott | | |
| street & number | 2410 Plum I | oint Road | telephone | no.: |
| city, town | Huntingtown | stat | e and zip codeMary | land 20639 |
| 5. Loca | ation of Leg | gal Descript | ion | |
| courthouse, regi | stry of deeds, etc. Ca | lvert County Co | urthouse | liber |
| street & number | Ma | in Street (MD 765) | | folio |
| city, town | Prince Frederic | • | state | Maryland |
| 6. Rep | resentatior | in Existing | Historical Sur | veys |
| title | | | | |
| date | | | federal sta | ate county loca |
| pository for su | ırvey records | | | |
| city, town | | | state | |

7. Description

Survey No. CT-785

| X excellent deteriorated unaltered X original site good ruins X altered moved date of move fair unexposed | good ruins | | _ | |
|--|------------|--|---|--|
|--|------------|--|---|--|

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Trott House is located on the northwest corner of Plum Point Road (Maryland Route 263) and Evans Road, approximately $\frac{1}{2}$ mile northeast of the rural community of Parran and five miles northeast of Prince Frederick.

The Trott House is a two story frame house of the "four-square" style. It was constructed in 1927 using a slightly modified plan from a Sears and Roebuck catalogue. The house measures approximately 26 feet by 28 feet and is two bays wide and two rooms deep with a single brick chimney centered at the peak of a pyramidal roof.

The front facade faces east to the Plum Point Road. The front door is located in the south or left bay of the first story, with a triple 6/l bank of windows to the right. Paired 6/l windows are located to left and right on the second story. A plain one story hip roof porch stretches across the front facade. The building rests on a poured concrete foundation and is covered with aluminum siding, which was added eight or ten years ago and covers original plain weatherboard siding. The eaves are boxed in; the roof is covered with "Cartwright" stamped metal roofing, which replaced a composition shingle roof of circa 1948.

The fenestration on the north and south facades is asymmetrical and includes a mixture of 6/1 sash, paired 6/1 sash, and smaller six-light windows.

On the rear facade there is a one story enclosed porch across the first story and two 6/1 windows on the second story.

The interior utilizes a three room plan on the first story and a four room plan on the second story. On the first floor, a large rectangular living room stretches across the east or front with doors opening into two rooms to the rear. The room to the north is slightly larger and serves as the dining room, while the smaller room to the south was originally the kitchen. A rear porch across the west facade has been enclosed and the south end now serves as the kitchen.

| 8. Sigr | nificance | | Survey No. C | T-785 |
|---|---|-------------------|--|--|
| Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 1800–1899X 1900– | archeology-historic agriculture _X architecture art | | Iandscape architect Iaw Iiterature Immunitary Impulsic Indicates philosophy Indicates politics/governmen | science sculpture social/ humanitarian |
| Specific dates | 1927 | Builder/Architect | | |
| App1 | licable Criteria:A and/or licable Exception:A | A _B _C _D _E | E _F _G | |

8. Significance

Prepare both a summary paragraph of significance and a general statement of history and support.

The Trott House is a two story frame house of the "foursquare" style that was constructed using plans purchased from a Sears and Roebuck catalogue. The house was built by Robert E. Trott in 1927 and has been continuously occupied by Mr. and Mrs. Trott since the house was completed in November of that year.

Mr. Trott recalls that he purchased the land in 1925, five years after their marriage in December 1920, and that construction began in the winter of 1927. He purchased the plans from Sears but did not buy the house materials because he had his own timber and a sawmill. The only materials he purchased were doors, windows, flooring, plaster lathing, cement, bricks and roofing. All other lumber was prepared on the site. The cellar was excavated with a team of horses and a drag scoop. Much of the work was done by Mr. Trott with assistance at times from his brother-in-law and his neighbors. He also hired a good carpenter for \$5.00 per day. The total cost of the house including labor and materials was about \$2500.

In 1930, Mr. Trott sold 35 acres of land on the southeast side of Plum Point Road to Arthur Gibson. Mr. Gibson used the same Sears plans to build a house on this property that still stands and is visible from Mr. Trott's house, located several hundred yards to the southwest and on the opposite side of Plum Point Road. Mr. Trott made minor modifications to the plans and it would appear that Arthur Gibson did as well.

| 10. Ge | ograph | ical Data | a | | |
|-----------------|----------------------------|--------------------|---------|---------------------|------------------|
| Quadrangle nam | ne Prince F | rederick, MD | erences | Quadrang | le scale 1:24000 |
| Zone Easti | ing | Northing | BZon | e Easting | Northing |
| C | <u>. </u> . <u> </u> | | D | | |
| | | n and justificatio | | r county boundaries | |
| state | | code | county | | code |
| state | | code | county | | code |
| 11. Fo | rm Pre | pared By | | | |
| name/title | Orlando 1 | Ridout V | | | |
| organization | Maryland | Historical | Trust | date | |
| street & number | 21 St. | ate Circle | = + | telephone | 7. ** ** ** |
| ity or town | Annapo | lis | 1, 9 | state Maryland | |
| | | | | , | |

Field Notebook MD-9; Recorded October 7, 1983. The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401


(301) 269-2438

7.1 DESCRIPTION

The stair to the second floor rises against the south wall of the living room to a central passage on the second story that bisects the upper floor from south to north. There are two sleeping chambers on either side of the hall and a modern bath at the north end.

Mr. Trott recalls making several modifications in the Sears plan. The original plans were for a house 26 feet by 24 feet, but Mr. Trott enlarged it slightly to 28feet by 26 feet. He also added a landing near the top of the stairs in place of the winder steps called for in the plans.

Barns: There are three barns on the property, all built by Mr. Trott. An earlier barn on the farm was located on the south side of Evans Road but has been demolished.





CT-785 Robert Trott House
Huntingtown vicinity
Orlando Ridout V
October 7, 1983
View from Southeast



CT-785 Robert Trott House
Huntingtown vicinity
Orlando Ridout V
October 7, 1983
View from Southwest